



Southern Cross Care


# Carmelite Stage 2 Development

## STORMWATER MANAGEMENT PLAN

WGA230682

WGA230682-RP-CV-0001\_B

3 November 2025



### Revision History

| REV | DATE       | ISSUE          | ORIGINATOR | CHECKER | APPROVER |
|-----|------------|----------------|------------|---------|----------|
| A   | 29/08/2025 | Approval Issue | CH         | CH      | CH       |
| B   | 3/11/2025  | Updated        | CH         | CH      | CH       |
|     |            |                |            |         |          |
|     |            |                |            |         |          |

# CONTENTS

|       |   |   |
|-------|---|---|
| 1     | INTRODUCTION .....                      | 1 |
| 1.1   | Background .....                        | 1 |
| 1.2   | Scope of the Assessment .....           | 1 |
| 1.2.1 | Documentation .....                     | 1 |
| 2     | DETAILED REPORT .....                   | 2 |
| 2.1   | Development Description .....           | 2 |
| 2.2   | Catchment Description .....             | 2 |
| 2.3   | Existing Stormwater Drainage .....      | 4 |
| 2.4   | Council Requirements .....              | 5 |
| 2.5   | Stormwater Management Methodology ..... | 5 |
| 2.6   | Summary .....                           | 6 |

## Figures

|           |  |   |
|-----------|--|---|
| Figure 1: | Northern Side of Site Looking East from Northern Boundary .....                  | 2 |
| Figure 2: | Existing Arch Bishop's Residence Looking South-West from Northern Boundary ..... | 3 |
| Figure 3: | Eastern Side of Site Looking South-from Northern Boundary .....                  | 3 |
| Figure 4: | Existing Arch Bishop's Residence Looking -West from Eastern Boundary .....       | 4 |
| Figure 5: | Existing Detention Basin .....   | 5 |

## Appendices

- Appendix A** ARCHITECTURAL DRAWINGS
- Appendix B** AERIAL PHOTOGRAPHS
- Appendix C** ENGINEERING SURVEY
- Appendix D** EXISTING STORMWATER DRAINAGE
- Appendix E** PRELIMINARY STORMWATER PLAN

# 1 INTRODUCTION

## 1.1 Background

Wallbridge Gilbert Aztec (WGA) has been engaged by Southern Cross Care to prepare a preliminary stormwater management report for the proposed Stage 2 development at the Carmelite site in Myrtle Bank.

This report is intended to conceptually outline the stormwater design for the proposed development and detail the stormwater management methodology. A final detailed design should be carried out to provide construction documentation and incorporate the stormwater design principles outlined in this report. The final documentation is considered to be beyond the scope of this report.

## 1.2 Scope of the Assessment

The preparation of the plan comprises the scope of services listed below:

- Site visit.
- Prepare a Stormwater Management Plan detailing the proposed method of collection, treatment and the disposal of site generated stormwater runoff.
- Prepare a preliminary sketch plan showing possible site drainage infrastructure based on the Council's requirements.

### 1.2.1 Documentation

The client has provided preliminary Architectural plans for the development and an engineering survey.

# 2 DETAILED REPORT

## 2.1 Development Description

It is understood the proposed development comprises the construction of a two multi-storey apartment buildings, including the creation of undercroft and basement car parking areas, extensive landscaping and internal roads and on-grade car parking areas. Refer to Appendix A for a copy of the preliminary site plans prepared by Walter Brooke and Associates.

## 2.2 Catchment Description

The site is located on the north-western corner of Glen Osmond Road and Cross Road in Myrtle Bank. It is bordered by Spence Avenue to the west and the Glen Woodley Estate to the north.

Currently the site is mostly vacant. Several buildings were demolished in 2018, leaving the Arch Bishop's Residence as the only remaining building. The rest of the development consists of unsealed informal roads and hardstand areas and landscaping. Refer to Appendix B for a copy of the current aerial photo.

The proposed site for the new development is steep with falls typically from south-east to north-west. There is a fall of approx 10m over 200m. Refer to Appendix C for a copy of the engineering survey that shows the site levels.

Below are photos that show the current site conditions.



**Figure 1: Northern Side of Site Looking East from Northern Boundary**



**Figure 2: Existing Arch Bishop's Residence Looking South-West from Northern Boundary**



**Figure 3: Eastern Side of Site Looking South-from Northern Boundary**



**Figure 4: Existing Arch Bishop's Residence Looking -West from Eastern Boundary**

### **2.3 Existing Stormwater Drainage**

The main existing stormwater infrastructure is a detention basin located to the western side of the site. This is approx. 260m<sup>3</sup> in volume and is associated with the existing Stage 1 development. Several stormwater pipes discharge into the basin on the southern side (from Stage 1) and there are also pipes that enter from the north (that are associated with more informal swales on the northern boundary).

There is a 1500mm dia stormwater pipe running through the site (falling south to north) that collects stormwater runoff from catchments further upstream of the development site. This pipe ultimately discharges into a basin and creek system in Ridge Park further north of the site.

Refer to Appendix D for details of the existing stormwater drains and the photo below showing the existing detention basin.



**Figure 5: Existing Detention Basin**

## **2.4 Council Requirements**

Discussions with Russell King (Senior Assets & Infrastructure Lead) at the City of Unley has indicated Council's preference that all stormwater run-off from the site is ultimately connected to their aquifer recharge and re-use site at Ridge Park and that detention requirements and designs are driven only by the capacity of the existing 1500mm diameter pipe main to carry the site's additional stormwater.

Council have advised that the existing detention basin at Ridge Park is able to achieve the required stormwater attenuation for the catchment and, as such, no detention storage is required for this Stage 2 development.

## **2.5 Stormwater Management Methodology**

To address Council requirements, a preliminary stormwater management methodology has been prepared for the development and is outlined below.

Stormwater runoff from the new buildings will be collected by roof gutters and downpipes which will be connected to a series of underground stormwater pipes. Surface runoff from the new pavements will also be collected by grated inlet pits, trench grates and similar and connected to the underground stormwater system.

New underground stormwater drainage for Stage 2 will connect to the existing 1500mm dia stormwater pipe (in the north-western corner of the site).


It is noted that the new development will impact on the existing stormwater detention basin constructed as part of Stage 1. The basin capacity is approximately 260m<sup>3</sup>. The stormwater pipework currently entering this basin will need to be re-directed as part of the Stage 2 work and the basin capacity replicated elsewhere on site (likely in the form of underground tanks). Two large pipes entering the existing basin must be intercepted to control and re-direct the Stage 1 stormwater run-off.

Refer to Appendix E for a copy of the sketch plan showing the proposed methodology of stormwater collection and disposal.

## **2.6 Summary**

The Preliminary sketch plan contained within this report has been prepared to demonstrate the philosophy behind proposed management of the stormwater runoff from this development. The information provided is preliminary and will be subject to detailed design and documentation.


**APPENDIX A**  
ARCHITECTURAL DRAWINGS





| REASON FOR ISSUE | REV | DATE       | SITE PLAN - OVERALL |
|------------------|-----|------------|---------------------|
| For Approval     | A   | 29-10-2025 | 1:350               |






DRAWN BY: Andrew O'Leary DATE: 29-10-2025 11:44:41 AM Client: Land & Planning, Carmelite Stage 2, Adelaide, SA, Australia


**SITE PLAN - LOWER**


| REASON FOR ISSUE | REV | DATE       |
|------------------|-----|------------|
| For Approval     | A   | 29-10-2025 |







**APPENDIX B**  
AERIAL PHOTOGRAPHS





**APPENDIX C**  
ENGINEERING SURVEY





**DETAIL AND LEVEL SURVEY  
CARMELITIE  
MYRTLE BANK, SA**




Land Development Made Easy

Phone: (08) 8440 2412  
Email: info@360surveying.com.au

**Notes:**  
Property boundaries shown have been compiled from government records and have not been verified by field survey.  
The location of underground service data shown has been determined by Fleureau Subsurface. All services must be verified before any construction or excavation. 360 Surveying is not liable for any errors or omissions.

**SCALE**



**COORDINATE SYSTEM**

VERTICAL: AHD  
HORIZONTAL: GROUND  
TO: MGA 2020 ZONE 54  
SCALE: GROUND (CSF = 1.00014971)


**CONTOUR INTERVAL: 0.5m / 2.0m**

SURVEY: TS/JDF SEPT 2023  
DRAWN: CF 12/09/2023  
CHECKED: TSJ 15/09/2023  
ORIGINAL SHEET SIZE A1

| Legend |                              |
|--------|------------------------------|
|        | Sewer MH / Sewer IP          |
|        | Water Topstone               |
|        | Gas Topstone                 |
|        | Electricity Topstone         |
|        | Telecom Topstone             |
|        | Gas Meter                    |
|        | Water Meter                  |
|        | Air Conditioning Unit        |
|        | Bollard                      |
|        | Bonhole                      |
|        | Drainage Downpipe            |
|        | Drainage Grating             |
|        | Electrical Cable Marker      |
|        | Fence Post                   |
|        | Hydrant                      |
|        | Irrigation Sprinkler         |
|        | Irrigation Control Valve     |
|        | Light Pole / In Ground Light |
|        | Road Sign                    |
|        | Stormwater MH                |
|        | Telecom Cable Marker         |
|        | Water Tap                    |
|        | One Sided Sign               |
|        | Two Sided Sign               |
|        | Shrub                        |
|        | Tree                         |
|        | Significant Tree             |
|        | Survey Station               |

DRAWING No. T013023 DETAIL(0) SHEET 1 OF 4 REVISION 0

| REV | DATE | DESCRIPTION | CALC | FIELD |
|-----|------|-------------|------|-------|
|     |      | AMENDMENTS  |      |       |



**DETAIL AND LEVEL SURVEY  
CARMELITIE  
MYRTLE BANK, SA**




Land Development Made Easy

Phone: (08) 8440 2412  
Email: info@360surveying.com.au

**Notes:**  
Property boundaries shown have been compiled from government records and have not been verified by field survey.  
The location of underground service data shown has been determined by Fleureau Subsurface. All services must be verified before any construction or excavation. 360 Surveying is not liable for any errors or omissions.

**COORDINATE BASE**  
PSM 6628/15167 E: 133.105  
N: 284610.651  
PSM 6628/9255 RL: 6128441.670  
SDB denotes SA Government survey data base values (Dated: 03/09/2023)

**SCALE**



**COORDINATE SYSTEM**

VERTICAL: AHD  
HORIZONTAL: GROUND  
TO: MGA 2020 ZONE 54  
SCALE: GROUND (CSF = 1.00014971)  
© 360 Surveying

**CONTOUR INTERVAL: 0.5m / 2.0m**

SURVEY: TS/JDF SEPT 2023  
DRAWN: CF 12/09/2023  
CHECKED: TSJ 15/09/2023  
ORIGINAL SHEET SIZE A1


|  |                  |  |                   |
|--|------------------|--|-------------------|
|  | Building / Wall  |  | ELEC Underground  |
|  | Edge Bitumen     |  | GAS Underground   |
|  | Edge Concrete    |  | SEWER Underground |
|  | Edge Track       |  | COMMS Underground |
|  | Fence            |  | WATER Underground |
|  | Gate             |  | RAIL TRACKS       |
|  | Change of Grade  |  | Kerb Top          |
|  | Top of Bank      |  | Natural Surface   |
|  | Bottom of Bank   |  | OHV Structure     |
|  | Stormwater Drain |  | Top Height        |
|  | Spous Drain      |  | Water Table       |
|  |                  |  | Invert Level      |

**Legend**

|  |                              |  |                          |
|--|------------------------------|--|--------------------------|
|  | Sewer MH / Sewer IP          |  | Air Conditioning Unit    |
|  | Water Topstone               |  | Bollard                  |
|  | Gas Topstone                 |  | Borehole                 |
|  | Electricity Topstone         |  | Drainage Downpipe        |
|  | Telecom Topstone             |  | Drainage Grating         |
|  | Gas Meter                    |  | Electrical Cable Marker  |
|  | Water Meter                  |  | Fence Post               |
|  |                              |  | Hydrant                  |
|  |                              |  | Irrigation Sprinkler     |
|  |                              |  | Irrigation Control Valve |
|  | Light Pole / In Ground Light |  | Road Sign                |
|  | Stormwater M&H               |  | Telecom Cable Marker     |
|  | Water Tap                    |  | One Sided Sign           |
|  | Shrub                        |  | Two Sided Sign           |
|  | Tree                         |  | Significant Tree         |
|  | Survey Station               |  |                          |

DRAWING No. T013023 DETAIL(0) SHEET 3 OF 4 REVISION 0

| REV        | DATE | DESCRIPTION | CALC | FIELD |
|------------|------|-------------|------|-------|
| AMENDMENTS |      |             |      |       |



CROSS

# DETAIL AND LEVEL SURVEY CARMELITIE MYRTLE BANK, SA



Land Development Made Easy

**Notes:**  
Property boundaries shown have been compiled from government records and have not been verified by field survey.  
The location of underground service data shown has been determined by Fleureau Subsurface. All services must be verified before any construction or excavation. 360 Surveying is not liable for any errors or omissions.


**COORDINATE BASE**  
PSM 6628/15167 E: 133.105  
N: 284610.651  
PSM 6628/9255 RL: 6128441.670

**COORDINATE SYSTEM**  
VERTICAL: AHD  
HORIZONTAL: GROUND  
TO: MGA 2020 ZONE 54

**SCALE: GROUND (CSF = 1.00014971)**

**CONTOUR INTERVAL: 0.5m / 2.0m**  
SURVEY: TS/JDF SEPT 2023  
DRAWN: CF  
CHECKED: TSJ 15/09/2023

**ORIGINAL SHEET SIZE A1**




| Legend |                              |
|--------|------------------------------|
|        | Sewer MH / Sewer IP          |
|        | Water Topstone               |
|        | Electricity Topstone         |
|        | Telecom Topstone             |
|        | Gas Meter                    |
|        | Water Meter                  |
|        | Air Conditioning Unit        |
|        | Bollard                      |
|        | Borehole                     |
|        | Drainage Downpipe            |
|        | Drainage Grating             |
|        | Electrical Cable Marker      |
|        | Fence Post                   |
|        | Hydrant                      |
|        | Irrigation Sprinkler         |
|        | Irrigation Control Valve     |
|        | Light Pole / In Ground Light |
|        | Road Sign                    |
|        | Stormwater MSH               |
|        | Telecom Cable Marker         |
|        | Water Tap                    |
|        | One Sided Sign               |
|        | Two Sided Sign               |
|        | Shrub                        |
|        | Tree                         |
|        | Significant Tree             |
|        | Survey Station               |


DRAWING No. T013023 DETAIL(0) SHEET 4 OF 4 REVISION 0

Phone: (08) 8440 2412  
Email: info@360surveying.com.au

| REV | DATE | DESCRIPTION | CALC | FIELD |
|-----|------|-------------|------|-------|
|     |      |             |      |       |

**APPENDIX D**  
EXISTING STORMWATER  
DRAINAGE







1500mm dia RCP

1500mm dia RCP

Myrtle Bank


**APPENDIX E**  
PRELIMINARY STORMWATER PLAN





W:\projects\2025\250608 - Southern Cross Carmelite Stage 2\Drawings\WGA230682-SK-CV-0011.dwg, 3/11/2025 2:20 PM, d:\admin

When sheet printed full size, the scale bar is 100mm.



**PRELIMINARY ISSUE**  
 NOT FOR CONSTRUCTION

| REV | DATE     | DESCRIPTION       | DRAFT | ENG.   | CHKD   |
|-----|----------|-------------------|-------|--------|--------|
| A   | 24.08.25 | PRELIMINARY ISSUE | C.H   | C.HILL | C.HILL |
| B   | 03.11.25 | UPDATED LAYOUT    | C.H   | C.HILL | C.HILL |



**CARMELETE - STAGE 2**  
 SOUTHERN CROSS CARE  
 7 SPENCE AVENUE, MYRTLE BANK S.A. 5064  
**STORMWATER MANAGEMENT PLAN**

**A1** DOCUMENT NUMBER  
 Project Number Sheet No. Rev.  
 Design WRS Drawn JPF  
**WGA230682-SK-CV-0011 B**

# WGA

FOR FURTHER INFORMATION CONTACT:

Colin Hill  
Principal Civil Engineer

T 08 8223 743  
E [chill@wga.com.au](mailto:chill@wga.com.au)

[WGA.COM.AU](http://WGA.COM.AU)  
[WGANZ.CO.NZ](http://WGANZ.CO.NZ)

